

Telephone: (02) 4306 7900
Please Quote: DA/1728/2025
Responsible Officer: Nick Bennet

S J Langlar
68 Broadwater Dr
SARATOGA NSW 2251

Notice of Determination of a Development Application
issued under the *Environmental Planning and Assessment Act 1979*
Sections 4.16, 4.17 and 4.18(1)(a)

Development Application No: DA/1728/2025
Applicant: S J Langlar
Property Address: Lot 26 Sec 5 DP 19850
42 Gwendolen Avenue, UMINA BEACH
Proposal: New 2 Storey Dwelling with Secondary Dwelling & Pool -
Includes Demolition Existing Dwelling - Staged Development
Determination: Approved
Determination Date: 26 March 2026.

Date from which this consent operates

In accordance with Section 4.20 of the *Environmental Planning and Assessment Act 1979*, this consent becomes effective and operates from the date of this notice being 26 March 2026.

Consent to lapse on

26 March 2031

Imposition of conditions

Subject to the provisions of Section 4.17 of the Act this Consent has been granted subject to conditions annexed to this consent.

Review of Determination

Subject to provisions of Sections 8.2, 8.3, 8.4 and 8.5 of the Act the applicant may make an application seeking a review of this determination, providing it is made in time for Council to determine the review within six (6) months of this determination.

Right of Appeal

Sections 8.7 and 8.10 of the Act confers on an applicant who is dissatisfied with the determination of a consent authority a right of appeal to the Land and Environment Court within six (6) months, from the date of determination.

On behalf of the consent authority

David Farmer

Chief Executive Officer

Per:

A handwritten signature in dark ink, appearing to read 'Nick Bennet', is written over a light blue rectangular background.

Nick Bennet

Building Surveyor

Building Assessment & Certification

STAGE 1: The following conditions apply to Stage 1 of the development consisting of Erection of a secondary dwelling

1. PARAMETERS OF THIS CONSENT

Approved Plans and Supporting Documentation

- 1.1. Development must be carried out in accordance with the following approved plans and supporting documentation (stamped by Council), except where the conditions of this consent expressly require otherwise.

Plan No.	Revision No.	Plan Title	Drawn By	Dated
Sheets 1-16	F	Architectural Plans	Inspiring Designs	05/02/2026

In the event of any inconsistency between the approved plans and the supporting documentation, the approved plans prevail. In the event of any inconsistency between the approved plans and a condition of this consent, the condition prevails.

Note: an inconsistency occurs between an approved plan and supporting documentation or between an approved plan and a condition when it is not possible to comply with both at the relevant time.

- 1.2. Carry out all building works in accordance with the National Construction Code Series, Building Code of Australia, Volume 1 and 2 as appropriate.
- 1.3. Comply with all commitments listed in the BASIX Certificate for the development as required under Section 75 *Environmental Planning and Assessment Regulation 2021*.

2. PRIOR TO ISSUE OF ANY CONSTRUCTION CERTIFICATE

- 2.1. All conditions under this section must be met prior to the issue of any Construction Certificate.
- 2.2. No activity is to be carried out on-site until the Construction Certificate has been issued, other than:
- a) Site investigation for the preparation of the construction, and / or
 - b) Implementation of environmental protection measures, such as erosion control and the like that are required by this consent
 - c) Demolition.

2.3. Before the issue of a construction certificate, the applicant must ensure a construction site management plan is prepared before it is provided to and approved by the certifier. The plan must include the following matters:

- location and materials for protective fencing and hoardings to the perimeter on the site
- provisions for public safety
- pedestrian and vehicular site access points and construction activity zones
- details of construction traffic management, including proposed truck movements to and from the site and estimated frequency of those movements, and measures to preserve pedestrian safety in the vicinity of the site
- protective measures for on-site tree preservation (including in accordance with AS 4970-2009 Protection of trees on development sites and Council's DCP, if applicable) and trees in adjoining public domain (if applicable)
- details of any bulk earthworks to be carried out
- location of site storage areas and sheds
- equipment used to carry out all works
- a garbage container with a tight-fitting lid
- dust, noise and vibration control measures
- location of temporary toilets.

The applicant must ensure a copy of the approved construction site management plan is kept on-site at all times during construction.

2.4. Before the issue of a construction certificate, the applicant is to ensure that a waste management plan is prepared in accordance with the EPA's Waste Classification Guidelines and the following requirements before it is provided to and approved by the certifier:

(a) Council's Waste Management Development Control Plan **OR**

(b) details the following:

- the contact details of the person(s) removing the waste
- an estimate of the waste (type and quantity) and whether the waste is expected to be reused, recycled or go to landfill
- the address of the disposal location(s) where the waste is to be taken.

The applicant must ensure the waste management plan is referred to in the construction site management plan and kept on-site at all times during construction.

2.5. Submit an application to Council under section 305 of the Water Management Act 2000 for a section 306 Requirements Letter. The Application form can be found on Council's website centralcoast.nsw.gov.au. Early application is recommended.

The section 305 application will result in a section 306 letter of requirements which must be obtained prior to the issue of any Construction Certificate. The requirements letter will outline which requirements must be met prior to each development milestone e.g. prior to construction certificate, subdivision works certificate, occupation certificate and/or subdivision certificate.

- 2.6. Pursuant to Section 7.11 of the *Environmental Planning and Assessment Act 1979*, pay to Council a total contribution amount of **\$9944.05**, that may require adjustment at the time of payment, in accordance with the relevant Council Contribution Plans No. 31A, 31B, 31C & 31D - Peninsula.

CP 31A - Peninsula - Roadworks	\$ 549.85
CP 31A - Peninsula - Open Space - Land	\$ 1,470.00
CP 31A - Peninsula - Open Space - Embellishment	\$ 5,016.85
CP 31A - Peninsula - Community Facilities - Land	\$ 72.00
CP 31A - Peninsula - Community Facilities - Capital	\$ 1,407.45
CP 31A - Peninsula - Drainage - Land	\$ 244.00
CP 31A - Peninsula - Drainage - Capital	\$ 1,183.90
TOTAL	\$ 9,944.05

The total amount must be indexed each quarter in accordance with the Consumer Price Index (All Groups Index) for Sydney issued by the Australian Statistician as outlined in the contributions plan.

Contact Council's Contributions Planner on (02) 4306 7900 for an up-to-date contribution payment amount.

Any Construction Certificate must not be issued until the developer has provided the Certifier with a copy of a receipt issued by Council that verifies that the contributions have been paid. A copy of this receipt must accompany the documents submitted by the certifying authority to Council under Clause 104/160(2) of the *Environmental Planning and Assessment Regulation 2000* **OR** Section 59 *Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021*.

A copy of the Contribution Plan may be inspected at the office of Central Coast Council, 2 Hely Street Wyong or on Council's website: [Development Contributions - former Gosford LGA](#)

3. PRIOR TO COMMENCEMENT OF ANY WORKS

- 3.1. All conditions under this section must be met prior to the commencement of any works.
- 3.2. Appoint a Principal Certifier for the building work:
 - a) The Principal Certifier (if not Council) is to notify Council of their appointment and notify the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work no later than two (2) days before the building work commences.
 - b) Submit to Council a Notice of Commencement of Building Work form giving at least two (2) days' notice of the intention to commence building work. The forms can be found on Council's website: www.centralcoast.nsw.gov.au

- 3.3. Erect a sign in a prominent position on any work site on which building, subdivision or demolition work is being carried out. The sign must indicate:
- a) The name, address and telephone number of the Principal Certifier for the work; and
 - b) The name of the principal contractor and a telephone number at which that person can be contacted outside of working hours; and
 - c) That unauthorised entry to the work site is prohibited.
 - d) Remove the sign when the work has been completed.
- 3.4. Submit both a Plumbing and Drainage Inspection Application, with the relevant fee, and a Plumbing and Drainage Notice of Work in accordance with the *Plumbing and Drainage Act 2011* (to be provided by licensed plumber). These documents can be found on Council's website at: www.centralcoast.nsw.gov.au
- Contact Council prior to submitting these forms to confirm the relevant fees.
- This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage). This condition does not apply to swimming pool plumbing that does not physically connect / break into the sewer system.
- 3.5. Provide and maintain a garbage receptacle at the work site until the works are completed. The garbage receptacle must have a tight-fitting lid and be suitable for food scraps and papers.
- 3.6. Install run-off and erosion controls to prevent soil erosion, water pollution or the discharge of loose sediment on the surrounding land by:
- erecting a silt fence and providing any other necessary sediment control measures that will prevent debris escaping into drainage systems, waterways or adjoining properties, and
 - diverting uncontaminated run-off around cleared or disturbed areas, and
 - preventing the tracking of sediment by vehicles onto roads, and
 - stockpiling top soil, excavated materials, construction and landscaping supplies and debris within the lot.
- 3.7. Disconnect, seal and make safe all existing site services prior to the commencement of any demolition on the site. Sewer and water services must be disconnected by a licensed plumber and drainer with a Notice Of Work (NOW) submitted to Council's Plumbing and Drainage Section via email – admin.plumbinganddrainage@centralcoast.nsw.gov.au

Note: Existing water meter is not to be removed by demolisher / plumber. Water & Sewer are required for any proposed removal / disconnection of council asset.

- 3.8. Erect a temporary hoarding or temporary construction site fence between the work site and adjoining lands before the works begin and must be kept in place until after the completion of the works, if the works:
- a) could cause a danger, obstruction or inconvenience to pedestrian or vehicular traffic, or
 - b) could cause damage to adjoining lands by falling objects, or
 - c) involve the enclosure of a public place or part of a public place.

Note 1: A structure on public land or on or over a public road requires the prior approval of the relevant authority under the *Local Government Act 1993* or the *Roads Act 1993*, respectively.

Note 2: The *Work Health and Safety Act 2011* and *Work Health and Safety Regulation 2011* contain provisions relating to scaffolds, hoardings and other temporary structures.

- 3.9. Provide or make available toilet facilities at the work site before works begin and maintain the facilities until the works are completed at a ratio of one toilet plus one additional toilet for every twenty (20) persons employed at the site.

Each toilet must:

- a) be a standard flushing toilet connected to a public sewer, or
- b) have an on-site effluent disposal system approved under the Local Government Act 1993, or
- c) be a temporary chemical closet approved under the Local Government Act 1993.

4. DURING WORKS

- 4.1. All conditions under this section must be met during works.
- 4.2. The principal certifier must ensure that building work, demolition or vegetation removal is only carried out between:

7.00 am and 5.00 pm on Monday to Saturday.

The principal certifier must ensure building work, demolition or vegetation removal is not carried out on Sundays and public holidays, except where there is an emergency.

Unless otherwise approved within a construction site management plan, construction vehicles, machinery, goods or materials must not be delivered to the site outside the approved hours of site works.

Note: Any variation to the hours of work requires Council's approval.

- 4.3. While demolition or building work is being carried out, all such works must cease immediately if a relic or Aboriginal object is unexpectedly discovered. The applicant must notify the Heritage Council of NSW in respect of a relic and notify the Secretary of the Department of Planning, Industry and Environment and the Heritage Council of NSW in respect of an Aboriginal object. Building work may recommence at a time confirmed by either the Heritage Council of NSW or the Secretary of the Department of Planning, Industry and Environment.

In this condition:

“relic” means any deposit, artefact, object or material evidence that:

- (a) relates to the settlement of the area that comprises New South Wales, not being Aboriginal settlement, and
- (b) is of State or local heritage significance; and

“Aboriginal object” means any deposit, object or material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of the area that comprises New South Wales, being habitation before or concurrent with (or both) the occupation of that area by persons of non-Aboriginal extraction and includes Aboriginal remains. To ensure the protection of objects of potential significance

- 4.4. Implement and maintain all erosion and sediment control measures at or above design capacity for the duration of the construction works and until such time as all ground disturbed by the works has been stabilised and rehabilitated so that it no longer acts as a source of sediment.
- 4.5. Keep a copy of the stamped approved plans on-site for the duration of site works and make the plans available upon request to either the Principal Certifier or an officer of Council.
- 4.6. Notify Council when plumbing and drainage work will be ready for inspection(s) and make the work accessible for inspection in accordance with the *Plumbing and Drainage Act 2011*.

This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage).

- 4.7. Place all building materials, plant and equipment on the site of the development during the construction phase of the development so as to ensure that pedestrian and vehicular access within adjoining public roads, footpaths and reserve areas, is not restricted and to prevent damage to public infrastructure. Further, no construction work is permitted to be carried out within the road reserve unless the works are associated with a separate approval issued under the provisions of the *Roads Act 1993*.

5.8. While building work is being carried out, the applicant must undertake the development strictly in accordance with the commitments listed in the BASIX certificate(s) approved by this consent, for the development to which the consent applies.

- 4.9. Cease all excavation works if acid sulfate soils are identified until such time as details of mitigation and treatment measures are submitted to, and approved by, the Principal Certifier.

- 4.10. Connect downpipes and the associated stormwater disposal system to the site stormwater connection point immediately after the roof materials are positioned in order to prevent erosion of the site from roof water run-off. The Principal Certifier for the development must not issue a mandatory critical stage Compliance Certificate for framing unless connection of the site stormwater (or temporary system) has occurred.
- 4.11. Re-use, recycle or dispose of all building materials in accordance with the Waste Management Plan submitted with the subject application.

5. PRIOR TO ISSUE OF ANY OCCUPATION CERTIFICATE

- 5.1. All conditions under this section must be met prior to the issue of any Occupation Certificate.
- 5.2. Submit a Certificate of Compliance for all plumbing and drainage work and a Sewer Service Diagram showing sanitary drainage work (to be provided by licensed plumber) in accordance with the *Plumbing and Drainage Act 2011*.

This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage).

- 5.3. Obtain a satisfactory plumbing and drainage final inspection in accordance with the requirements of the *Plumbing and Drainage Act 2011*.

This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage). This condition does not apply to swimming pool plumbing that does not physically connect / break into the sewer system.

- 5.4. Complete the building in accordance with the relevant provisions and requirements of the National Construction Code Series.
- 5.5. Drain all roof water by a piped drainage line to an infiltration trench.

Note: Infiltration trench details are to be designed by a practicing engineer experienced in hydraulics. The design details are to cater for a 1 in 20 year Annual Exceedance Probability (AEP) storm event and are to allow for a minimum setback of three (3) metres from any sewer main and lot boundaries.

- 5.6. Install a rainwater tank with a minimum capacity of 2000 litres pertinent to the secondary dwelling & a rainwater tank with a minimum capacity of 4000 Litres pertinent to the principal dwelling. The tank should be fitted with suitable plumbing connections to collect rainwater from the roof areas as detailed within the approved development plans with suitable plumbing connections provided to collect rainwater from the roof area as detailed within the BASIX Certificate applicable to the development. The required rainwater tank is to be installed in accordance with the requirements of the National Plumbing and Drainage Code Australian Standard AS 3500 and must be provided with first flow diversion devices fixed to all inflows and a functioning pressure pump plumbed to service all fixtures as detailed within the BASIX Certificate applicable to the development. The required tank must be controlled in order that supplemental flow from domestic mains does not take place until the capacity of the tank has

been reduced to 20%. All overflow must be connected via piped drainage line to an infiltration trench.

Note: Infiltration trenches are to be designed by a practicing engineer experienced in hydraulics. The design details are to cater for a 1 in 20 year AEP storm event and are to allow for a minimum setback of three (3) metres from any sewer main and lot boundaries.

- 5.7. Provide mail receptacles appropriately numbered for each dwelling unit in the development, as well as for the managing body, in consultation with Australia Post.
- 5.8. Contact Council's Land Information Officer or email ask@centralcoast.nsw.gov.au for allocation of a street address for the Secondary Dwelling.
- 5.9. Submit certification from a qualified civil or structural engineer to Council stating that all slabs and / or footings within the zone of influence associated with Council stormwater system and / or drainage easement have been constructed in accordance with the Construction Certificate.
- 5.10. Construct the vehicle access crossing in accordance with the vehicle access crossing Notice of Determination issued by Council.
- 5.11. Obtain the Section 307 Certificate of Compliance under the *Water Management Act 2000* for water and sewer requirements for the development from Central Coast Council as the Water Supply Authority, prior to issue of the Occupation Certificate.

6. ONGOING

- 6.1. Insulate and / or isolate the motor, filter, pump and all sound producing equipment or fitting associated with or forming part of the pool filtering system so as not to create an offensive noise to the occupants of the adjoining premises as defined in the *Protection of the Environment Operations Act 1997*.
- 6.2. Operate and maintain all external lighting so as not to impact on any adjoining property.

7. PENALTIES

Failure to comply with this development consent and any condition of this consent may be a **criminal offence**. Failure to comply with other environmental laws may also be a **criminal offence**.

Where there is any breach Council may without any further warning:

- Issue Penalty Infringement Notices (On-the-spot fines);
- Issue notices and orders;
- Prosecute any person breaching this consent, and/or
- Seek injunctions/orders before the courts to retain and remedy any breach.

Warnings as to Potential Maximum Penalties

Maximum Penalties under NSW Environmental Laws include fines up to \$1.1 Million and/or custodial sentences for serious offences.

ADVISORY NOTES

- Discharge of sediment from a site may be determined to be a pollution event under provisions of the *Protection of the Environment Operations Act 1997*. Enforcement action may commence where sediment movement produces a pollution event.
- The following public authorities may have separate requirements in the following aspects:
 - Australia Post for the positioning and dimensions of mail boxes in new commercial and residential developments
 - Jemena Asset Management for any change or alteration to the gas line infrastructure
 - Ausgrid for any change or alteration to electricity infrastructure or encroachment within transmission line easements
 - Telstra, Optus or other telecommunication carriers for access to their telecommunications Infrastructure
 - Central Coast Council in respect to the location of water, sewerage and drainage services.
- Carry out all work under this Consent in accordance with SafeWork NSW requirements including the *Workplace Health and Safety Act 2011 No 10* and subordinate regulations, codes of practice and guidelines that control and regulate the development industry.
- Dial Before You Dig
Underground assets may exist in the area that is subject to your application. In the interests of health and safety and in order to protect damage to third party assets please contact Dial Before You Dig at www.1100.com.au or telephone on 1100 before excavating or erecting structures. (This is the law in NSW). If alterations are required to the configuration, size, form or design of the development upon contacting the Dial Before You Dig service, an amendment to the development consent (or a new development application) may be necessary. Individuals owe asset owners a duty of care that must be observed when working in the vicinity of plant or assets. It is the individual's responsibility to anticipate and request the nominal location of plant or assets on the relevant property via contacting the Dial Before You Dig service in advance of any construction or planning activities.
- Telecommunications Act 1997 (Commonwealth)
Telstra (and its authorised contractors) are the only companies that are permitted to conduct works on Telstra's network and assets. Any person interfering with a facility or installation owned by Telstra is committing an offence under the *Criminal Code Act 1995 (Cth)* and is liable for prosecution. Furthermore, damage to Telstra's infrastructure may result in interruption to the provision of essential services and significant costs. If you are aware of any works or proposed works which may affect or impact on Telstra's assets in any way, you are required to contact: Telstra's Network Integrity Team on phone number 1800 810 443.

- Install and maintain backflow prevention device(s) in accordance with Council's WS4.0 Backflow Prevention Containment Policy. This policy can be found on Council's website: www.centralcoast.nsw.gov.au

This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage)

STAGE 2: The following conditions apply to Stage 2 of the development consisting of Demolition of the primary dwelling house, Erection of a new primary dwelling house & Swimming Pool.

8. PARAMETERS OF THIS CONSENT

Approved Plans and Supporting Documentation

- 8.1. Development must be carried out in accordance with the following approved plans and supporting documentation (stamped by Council), except where the conditions of this consent expressly require otherwise.

Plan No.	Revision No.	Plan Title	Drawn By	Dated
Sheets 1-16	F	Architectural Plans	Inspiring Designs	05/02/2026

In the event of any inconsistency between the approved plans and the supporting documentation, the approved plans prevail. In the event of any inconsistency between the approved plans and a condition of this consent, the condition prevails.

Note: an inconsistency occurs between an approved plan and supporting documentation or between an approved plan and a condition when it is not possible to comply with both at the relevant time.

- 8.2. Carry out all building works in accordance with the National Construction Code Series, Building Code of Australia, Volume 1 and 2 as appropriate.
- 8.3. Comply with all commitments listed in the BASIX Certificate for the development as required under Section 75 *Environmental Planning and Assessment Regulation 2021*.

9. PRIOR TO ISSUE OF ANY CONSTRUCTION CERTIFICATE

- 9.1. All conditions under this section must be met prior to the issue of any Construction Certificate.

- 9.2. No activity is to be carried out on-site until the Construction Certificate has been issued, other than:
- a) Site investigation for the preparation of the construction, and / or
 - b) Implementation of environmental protection measures, such as erosion control and the like that are required by this consent
 - c) Demolition.
- 9.3. Before the issue of a construction certificate, the applicant must ensure a construction site management plan is prepared before it is provided to and approved by the certifier. The plan must include the following matters:
- location and materials for protective fencing and hoardings to the perimeter on the site
 - provisions for public safety
 - pedestrian and vehicular site access points and construction activity zones
 - details of construction traffic management, including proposed truck movements to and from the site and estimated frequency of those movements, and measures to preserve pedestrian safety in the vicinity of the site
 - protective measures for on-site tree preservation (including in accordance with AS 4970-2009 Protection of trees on development sites and Council's DCP, if applicable) and trees in adjoining public domain (if applicable)
 - details of any bulk earthworks to be carried out
 - location of site storage areas and sheds
 - equipment used to carry out all works
 - a garbage container with a tight-fitting lid
 - dust, noise and vibration control measures
 - location of temporary toilets.

The applicant must ensure a copy of the approved construction site management plan is kept on-site at all times during construction.

- 9.4. Before the issue of a construction certificate, the applicant is to ensure that a waste management plan is prepared in accordance with the EPA's Waste Classification Guidelines and the following requirements before it is provided to and approved by the certifier:
- (a) Council's Waste Management Development Control Plan **OR**
 - (b) details the following:
 - the contact details of the person(s) removing the waste
 - an estimate of the waste (type and quantity) and whether the waste is expected to be reused, recycled or go to landfill
 - the address of the disposal location(s) where the waste is to be taken.

The applicant must ensure the waste management plan is referred to in the construction site management plan and kept on-site at all times during construction.

- 9.5. Submit to Council as the Roads Authority an application for a vehicle access crossing including payment of the application fee.
- 9.6. Submit an application to Council under section 305 of the Water Management Act 2000 for a section 306 Requirements Letter. The Application form can be found on Council's website centralcoast.nsw.gov.au. Early application is recommended.

The section 305 application will result in a section 306 letter of requirements which must be obtained prior to the issue of any Construction Certificate. The requirements letter will outline which requirements must be met prior to each development milestone e.g. prior to construction certificate, subdivision works certificate, occupation certificate and/or subdivision certificate.

10. PRIOR TO COMMENCEMENT OF ANY WORKS

- 10.1. All conditions under this section must be met prior to the commencement of any works.
- 10.2. Appoint a Principal Certifier for the building work:
 - a) The Principal Certifier (if not Council) is to notify Council of their appointment and notify the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work no later than two (2) days before the building work commences.
 - b) Submit to Council a Notice of Commencement of Building Work form giving at least two (2) days' notice of the intention to commence building work. The forms can be found on Council's website: www.centralcoast.nsw.gov.au
- 10.3. Erect a sign in a prominent position on any work site on which building, subdivision or demolition work is being carried out. The sign must indicate:
 - a) The name, address and telephone number of the Principal Certifier for the work; and
 - b) The name of the principal contractor and a telephone number at which that person can be contacted outside of working hours; and
 - c) That unauthorised entry to the work site is prohibited.
 - d) Remove the sign when the work has been completed.
- 10.4. Submit both a Plumbing and Drainage Inspection Application, with the relevant fee, and a Plumbing and Drainage Notice of Work in accordance with the *Plumbing and Drainage Act 2011* (to be provided by licensed plumber). These documents can be found on Council's website at: www.centralcoast.nsw.gov.au

Contact Council prior to submitting these forms to confirm the relevant fees.

This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage). This condition does not apply to swimming pool plumbing that does not physically connect / break into the sewer system.

- 10.5. Provide and maintain a garbage receptacle at the work site until the works are completed. The garbage receptacle must have a tight-fitting lid and be suitable for food scraps and papers.
- 10.6. Install run-off and erosion controls to prevent soil erosion, water pollution or the discharge of loose sediment on the surrounding land by:
- erecting a silt fence and providing any other necessary sediment control measures that will prevent debris escaping into drainage systems, waterways or adjoining properties, and
 - diverting uncontaminated run-off around cleared or disturbed areas, and
 - preventing the tracking of sediment by vehicles onto roads, and
 - stockpiling top soil, excavated materials, construction and landscaping supplies and debris within the lot.
- 10.7. Disconnect, seal and make safe all existing site services prior to the commencement of any demolition on the site. Sewer and water services must be disconnected by a licensed plumber and drainer with a Notice Of Work (NOW) submitted to Council's Plumbing and Drainage Section via email – admin.plumbinganddrainage@centralcoast.nsw.gov.au

Note: Existing water meter is not to be removed by demolisher / plumber. Water & Sewer are required for any proposed removal / disconnection of council asset.

- 10.8. Erect a temporary hoarding or temporary construction site fence between the work site and adjoining lands before the works begin and must be kept in place until after the completion of the works, if the works:
- a) could cause a danger, obstruction or inconvenience to pedestrian or vehicular traffic, or
 - b) could cause damage to adjoining lands by falling objects, or
 - c) involve the enclosure of a public place or part of a public place.

Note 1: A structure on public land or on or over a public road requires the prior approval of the relevant authority under the *Local Government Act 1993* or the *Roads Act 1993*, respectively.

Note 2: The *Work Health and Safety Act 2011* and *Work Health and Safety Regulation 2011* contain provisions relating to scaffolds, hoardings and other temporary structures.

- 10.9. Provide or make available toilet facilities at the work site before works begin and maintain the facilities until the works are completed at a ratio of one toilet plus one additional toilet for every twenty (20) persons employed at the site.

Each toilet must:

- a) be a standard flushing toilet connected to a public sewer, or
- b) have an on-site effluent disposal system approved under the Local Government Act 1993, or
- c) be a temporary chemical closet approved under the Local Government Act 1993.

- 10.10. Undertake any demolition involving asbestos in accordance with the *Work Health and Safety Act 2011*.

The person having the benefit of this consent must ensure that the removal of:

- a) more than 10m² of non-friable asbestos or asbestos containing material is carried out by a licensed non-friable (Class B) or a friable (Class A) asbestos removalist, and
- b) friable asbestos of any quantity is removed by a licensed removalist with a friable (Class A) asbestos removal licence.

The licensed asbestos removalist must give notice to the regulator before work commences in accordance with Clause 466 of the *Work Health and Safety Regulation 2011*.

11. DURING WORKS

- 11.1. All conditions under this section must be met during works.

- 11.2. The principal certifier must ensure that building work, demolition or vegetation removal is only carried out between:

7.00 am and 5.00 pm on Monday to Saturday.

The principal certifier must ensure building work, demolition or vegetation removal is not carried out on Sundays and public holidays, except where there is an emergency.

Unless otherwise approved within a construction site management plan, construction vehicles, machinery, goods or materials must not be delivered to the site outside the approved hours of site works.

Note: Any variation to the hours of work requires Council's approval.

- 11.3. While demolition or building work is being carried out, all such works must cease immediately if a relic or Aboriginal object is unexpectedly discovered. The applicant must notify the Heritage Council of NSW in respect of a relic and notify the Secretary of the Department of Planning, Industry and Environment and the Heritage Council of NSW in respect of an Aboriginal object. Building work may recommence at a time confirmed by either the Heritage Council of NSW or the Secretary of the Department of Planning, Industry and Environment.

In this condition:

“relic” means any deposit, artefact, object or material evidence that:

- (a) relates to the settlement of the area that comprises New South Wales, not being Aboriginal settlement, and
- (b) is of State or local heritage significance; and

“Aboriginal object” means any deposit, object or material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of the area that comprises New South Wales, being habitation before or concurrent with (or both) the occupation of that area by persons of non-Aboriginal extraction and includes Aboriginal remains. To ensure the protection of objects of potential significance

- 11.4. Implement and maintain all erosion and sediment control measures at or above design capacity for the duration of the construction works and until such time as all ground disturbed by the works has been stabilised and rehabilitated so that it no longer acts as a source of sediment.
- 11.5. Keep a copy of the stamped approved plans on-site for the duration of site works and make the plans available upon request to either the Principal Certifier or an officer of Council.
- 11.6. Notify Council when plumbing and drainage work will be ready for inspection(s) and make the work accessible for inspection in accordance with the *Plumbing and Drainage Act 2011*.

This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage).

- 11.7. Place all building materials, plant and equipment on the site of the development during the construction phase of the development so as to ensure that pedestrian and vehicular access within adjoining public roads, footpaths and reserve areas, is not restricted and to prevent damage to public infrastructure. Further, no construction work is permitted to be carried out within the road reserve unless the works are associated with a separate approval issued under the provisions of the *Roads Act 1993*.
- 11.8. While building work is being carried out, the applicant must undertake the development strictly in accordance with the commitments listed in the BASIX certificate(s) approved by this consent, for the development to which the consent applies.
- 11.9. Cease all excavation works if acid sulfate soils are identified until such time as details of mitigation and treatment measures are submitted to, and approved by, the Principal Certifier.

- 11.10. Connect downpipes and the associated stormwater disposal system to the site stormwater connection point immediately after the roof materials are positioned in order to prevent erosion of the site from roof water run-off. The Principal Certifier for the development must not issue a mandatory critical stage Compliance Certificate for framing unless connection of the site stormwater (or temporary system) has occurred.
- 11.11. Re-use, recycle or dispose of all building materials in accordance with the Waste Management Plan submitted with the subject application.
- 11.12. Erect or install prior to the swimming pool being filled with water all the required swimming pool safety barriers and gates in accordance with the approved plans and specifications and the provisions of the *Swimming Pools Act 1992*, *Swimming Pools Regulation 2018* and Australian Standard AS 1926.1-2012 including the display of an approved sign regarding pool safety and resuscitation techniques that contains all of the following information:
- "YOUNG CHILDREN SHOULD BE SUPERVISED WHEN USING THIS SWIMMING POOL"
 - "POOL GATES MUST BE KEPT CLOSED AT ALL TIMES"
 - "KEEP ARTICLES, OBJECTS AND STRUCTURES AT LEAST 900mm CLEAR OF THE POOL FENCE AT ALL TIMES"
 - A simple flow sequence (which may be the flow sequence depicted in the Cardiopulmonary Resuscitation Guideline) containing details of resuscitation techniques (for infants, children and adults)
- 11.13. Do not fill the swimming pool with water until the common boundary fence forming part of the pool enclosure has been installed with a minimum height of 1.8 metres when measured inside the pool enclosure in accordance with the provisions of Australian Standard AS 1926.1 2012. The maintenance and effectiveness of the fence is the responsibility of the pool owner whilst ever the pool exists.
- Alternatively, the pool must be fully enclosed by swimming pool safety fencing complying with the provisions of Australian Standard AS 1926.1-2012 in lieu of any boundary fencing.
- 11.14. Dispose filter backwash and overflow to the sewer. The sewer connection must be completed prior to the filling of the pool with water and in a manner that will not cause a nuisance, or where sewer is not available, the disposal of filter backwash must be discharged into a rubble absorption trench to the satisfaction of the Principal Certifier.
- 11.15. Demolish all buildings and / or building components in a safe and systematic manner in accordance with Australian Standard AS 2601-2001: *The demolition of structures*. Waste materials must be disposed of at a waste management facility.
- 11.16. Do not fill the swimming pool with water until each window which is capable of giving access to the swimming pool enclosure has been protected with suitable security screens complying with the provisions of Clause 2.6 of Australian Standard AS 1926.1-2012. This applies to all windows where the height of the sill of the lowest openable portion of the window is less than 1.8 metres above the adjoining ground surface level.

12. PRIOR TO ISSUE OF ANY OCCUPATION CERTIFICATE

- 12.1. All conditions under this section must be met prior to the issue of any Occupation Certificate.
- 12.2. Submit a Certificate of Compliance for all plumbing and drainage work and a Sewer Service Diagram showing sanitary drainage work (to be provided by licensed plumber) in accordance with the *Plumbing and Drainage Act 2011*.

This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage).

- 12.3. Obtain a satisfactory plumbing and drainage final inspection in accordance with the requirements of the *Plumbing and Drainage Act 2011*.

This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage). This condition does not apply to swimming pool plumbing that does not physically connect / break into the sewer system.

- 12.4. Complete the building in accordance with the relevant provisions and requirements of the National Construction Code Series.

- 12.5. Drain all roof water by a piped drainage line to an infiltration trench.

Note: Infiltration trench details are to be designed by a practicing engineer experienced in hydraulics. The design details are to cater for a 1 in 20 year Annual Exceedance Probability (AEP) storm event and are to allow for a minimum setback of three (3) metres from any sewer main and lot boundaries.

- 12.6. Install a rainwater tank with a minimum capacity of 4000 Litres pertinent to the principal dwelling. The tank should be fitted with suitable plumbing connections to collect rainwater from the roof areas as detailed within the approved development plans with suitable plumbing connections provided to collect rainwater from the roof area as detailed within the BASIX Certificate applicable to the development. The required rainwater tank is to be installed in accordance with the requirements of the National Plumbing and Drainage Code Australian Standard AS 3500 and must be provided with first flow diversion devices fixed to all inflows and a functioning pressure pump plumbed to service all fixtures as detailed within the BASIX Certificate applicable to the development. The required tank must be controlled in order that supplemental flow from domestic mains does not take place until the capacity of the tank has been reduced to 20%. All overflow must be connected via piped drainage line to an infiltration trench.

Note: Infiltration trenches are to be designed by a practicing engineer experienced in hydraulics. The design details are to cater for a 1 in 20 year AEP storm event and are to allow for a minimum setback of three (3) metres from any sewer main and lot boundaries.

- 12.7. Provide mail receptacles appropriately numbered for each dwelling unit in the development, as well as for the managing body, in consultation with Australia Post.
- 12.8. Submit certification from a qualified civil or structural engineer to Council stating that all slabs and / or footings within the zone of influence associated with Council stormwater system and / or drainage easement have been constructed in accordance with the Construction Certificate.
- 12.9. Construct the vehicle access crossing in accordance with the vehicle access crossing Notice of Determination issued by Council.
- 12.10. Obtain the Section 307 Certificate of Compliance under the *Water Management Act 2000* for water and sewer requirements for the development from Central Coast Council as the Water Supply Authority, prior to issue of the Occupation Certificate.

13. ONGOING

- 13.1. Insulate and / or isolate the motor, filter, pump and all sound producing equipment or fitting associated with or forming part of the pool filtering system so as not to create an offensive noise to the occupants of the adjoining premises as defined in the *Protection of the Environment Operations Act 1997*.
- 13.2. Do not change the location of the Vehicle Access Crossing without prior written approval from Council.

14. PENALTIES

Failure to comply with this development consent and any condition of this consent may be a **criminal offence**. Failure to comply with other environmental laws may also be a **criminal offence**.

Where there is any breach Council may without any further warning:

- Issue Penalty Infringement Notices (On-the-spot fines);
- Issue notices and orders;
- Prosecute any person breaching this consent, and/or
- Seek injunctions/orders before the courts to retain and remedy any breach.

Warnings as to Potential Maximum Penalties

Maximum Penalties under NSW Environmental Laws include fines up to \$1.1 Million and/or custodial sentences for serious offences.

ADVISORY NOTES

- Discharge of sediment from a site may be determined to be a pollution event under provisions of the *Protection of the Environment Operations Act 1997*. Enforcement action may commence where sediment movement produces a pollution event.
- The following public authorities may have separate requirements in the following aspects:
 - a) Australia Post for the positioning and dimensions of mail boxes in new commercial and residential developments
 - b) Jemena Asset Management for any change or alteration to the gas line infrastructure
 - c) Ausgrid for any change or alteration to electricity infrastructure or encroachment within transmission line easements
 - d) Telstra, Optus or other telecommunication carriers for access to their telecommunications infrastructure
 - e) Central Coast Council in respect to the location of water, sewerage and drainage services.
- Carry out all work under this Consent in accordance with SafeWork NSW requirements including the *Workplace Health and Safety Act 2011 No 10* and subordinate regulations, codes of practice and guidelines that control and regulate the development industry.
- Dial Before You Dig
Underground assets may exist in the area that is subject to your application. In the interests of health and safety and in order to protect damage to third party assets please contact Dial Before You Dig at www.1100.com.au or telephone on 1100 before excavating or erecting structures. (This is the law in NSW). If alterations are required to the configuration, size, form or design of the development upon contacting the Dial Before You Dig service, an amendment to the development consent (or a new development application) may be necessary. Individuals owe asset owners a duty of care that must be observed when working in the vicinity of plant or assets. It is the individual's responsibility to anticipate and request the nominal location of plant or assets on the relevant property via contacting the Dial Before You Dig service in advance of any construction or planning activities.
- Telecommunications Act 1997 (Commonwealth)
Telstra (and its authorised contractors) are the only companies that are permitted to conduct works on Telstra's network and assets. Any person interfering with a facility or installation owned by Telstra is committing an offence under the *Criminal Code Act 1995 (Cth)* and is liable for prosecution. Furthermore, damage to Telstra's infrastructure may result in interruption to the provision of essential services and significant costs. If you are aware of any works or proposed works which may affect or impact on Telstra's assets in any way, you are required to contact: Telstra's Network Integrity Team on phone number 1800 810 443.
Install and maintain backflow prevention device(s) in accordance with Council's WS4.0 Backflow Prevention Containment Policy. This policy can be found on Council's website: www.centralcoast.nsw.gov.au

This condition only applies if installation / alteration of plumbing and / or drainage works are proposed (excludes stormwater drainage)